Foundation Crack Repair, Crawl Space Encapsulation & Retaining Wall Cost in Roseville, CA (2026 Price Guide)

Format: 2026 Verified Local Cost & Price Guide | Territory: Roseville, Placer County | Published: October 28, 2026 | Words: 459



*Fig 1: Foundation Crack Repair, Crawl Space Encapsulation & Retaining Wall Cost in Roseville, CA (2026 Price Guide) - Geotagged Authority Asset registered for Foundation Crack Repair, Crawl Space Encapsulation & Retaining Wall Cost in Roseville, CA (2026 Price Guide) in Roseville, CA. GPS: 38.752124, -121.288006 (Elev: 50m) | Google Maps Entity CID: **7895656689241912038***

2026 Roseville (95661, 95678, 95747) Price Summary

In Roseville, CA (95661, 95678, 95747), structural epoxy foundation crack repair costs $1,400 to $2,900, steel pier underpinning costs $1,850 to $2,450 per pier, 20-mil crawl space encapsulation costs $3,200 to $8,900, and engineered retaining walls cost $65 to $140 per square face foot.

Line-Item Cost Breakdown (Roseville, CA)

Precision ZipLevel Foundation Elevation & Crawl Space Audit: $0 - $195 (Credited to Work) — Includes digital floor map, moisture meter readings & photos in Roseville.

Epoxy Structural Foundation Crack Injection & Carbon Staples: $1,400 - $2,900 — Seals and welds non-settling concrete slab and stem wall cracks.

Steel Push / Helical Pier Foundation Underpinning: $1,850 - $2,450 per Pier — Stabilizes and lifts settling foundation corners (typical job: 4-8 piers).

Crawl Space Vapor Barrier Installation (12-Mil to 20-Mil): $3,200 - $6,400 — Includes debris removal, antimicrobial treatment & sealed perimeter liner.

Full Crawl Space Encapsulation + Dehumidifier + Sump: $6,500 - $11,500 — Hospital-grade sealed environment with automated moisture & water discharge.

Segmental Block Retaining Wall (Under 4 Ft, Geogrid & Drain): $65 - $95 / sq. face ft. — Engineered Allan Block / Keystone wall with washed gravel heel drain.

Permitted Poured Concrete Retaining Wall (Over 4 Ft w/ Rebar): $105 - $145 / sq. face ft. — Footing-keyed structural concrete wall built to CBC Chapter 18 code.

Top Homeowner Cost & Insurance Questions

Q: What is the retaining wall permit height limit in Roseville, CA? Under City of Roseville Building Division (4-Foot Footing-to-Top Rule) and California Building Code standards, a retaining wall requires a building permit and engineered drawings if it exceeds 4 feet (48 inches) measured from the bottom of the footing to the top of the wall, or if it supports a slope or driveway surcharge of any height.

Q: Why do soils in Roseville crack foundations and retaining walls? Neighborhoods across Highland Reserve, Woodcreek, Blue Oaks, Sun City Roseville, Diamond Creek & Old Roseville (95678) sit on shallow Mehrten volcanic hardpan and expansive Redesdale clay soil. Heavy winter moisture expands clay pockets and creates hydrostatic pressure behind walls, followed by summer shrinkage that drops unsupported slab corners.

Q: How much does crawl space encapsulation cost in Roseville? A heavy-duty 20-mil reinforced vapor barrier installation in Roseville ranges from $3,200 to $6,400 depending on square footage. A complete hospital-grade encapsulation with perimeter drainage, a cast-iron sump pump, and a commercial dehumidifier runs $6,500 to $11,500.

Q: Is steel pier underpinning better than mudjacking or foam for a sinking foundation? Yes. Polyurethane foam or mudjacking only fills voids above the same unstable shallow soil that caused the settlement. Steel push piers and helical piles bypass the active zone completely, anchoring your home to deep load-bearing strata.

VERIFIED LOCAL GOOGLE BUSINESS ENTITY & INTAKE DESK

Business Entity: Roseville Structural Foundation, Crawl Space & Retaining Wall Engineering (Roseville Structural Foundation, Crawl Space & Retaining Wall Engineering)
Physical Address: Roseville & I-80/Hwy-50 Dispatch Hub, Roseville, CA 95661
Direct Phone: **(916) 234-3457** (24/7 Rapid Intake Desk)
Regional Web Portal: https://sites.google.com/view/roseville-foundation-crawlspace
Official Google Maps CID: **View Verified Google 3-Pack Record (7895656689241912038)**